




CARROLL COUNTY



STATE GOALS: Maryland Transportation Plan (MTP) Goals/Selection Criteria: Serve Communities and Support the Economy

Enhance Safety and Security

Deliver System Quality Promote Environmental Stewardship

EXPLANATION: The existing bridges are nearing the end of their useful service life and are currently rated fair. Rehabilitation efforts are costly moving this to total replacement of both bridges.

PROJECT: MD 91, Emory Road

DESCRIPTION: Replacement of Bridge No. 0602000 on MD 91 over N. Branch Patapsco River and Bridge No. 0604700 on MD 91 over Maryland Midland Railroad.

PURPOSE & NEED SUMMARY STATEMENT: The purpose of this project is to replace fair rated bridges to prevent further deterioration to poor rating.

SMART GROWTH STATUS:	Project Not Location	Specific	Not Subject to PFA Law
X Project Inside PFA Project Outside PFA PFA Status Yet to Be Dete	ermined	Grandfathered Exception Will B Exception Grant	•

STATUS: Construction underway.

SIGNIFICANT CHANGE FROM FY 2023 - 28 CTP: The cost increase of \$2.2 million is due to an unfavorable bid on the construction contract.

POTENTIA	L FUNDING S	OURCE:		X SPECIAL		X FEDER	AL	GENERAL	OTHER		
	TOTAL										
PHASE	ESTIMATED	EXPENDED	EXPENDED	CURRENT	BUDGET	PRO	JECTED CAS	H REQUIREM	ENTS	SIX	BALANCE
	COST	THRU	IN	YEAR	YEAR	FOR	RPLANNING	PURPOSES C	NLY	YEAR	то
	(\$000)	2023	2023	2024	2025	2026	2027	2028	2029	TOTAL	COMPLETE
Planning	0	0	0	0	0	0	0	0	0	0	0
Engineering	1,324	1,300	320	24	0	0	0	0	0	24	0
Right-of-way	83	81	54	1	1	0	0	0	0	2	0
Utilities	0	0	0	0	0	0	0	0	0	0	0
Construction	13,165	11	11	8,690	4,464	0	0	0	0	13,154	0
Total	14,572	1,392	385	8,715	4,465	0	0	0	0	13,180	0
Federal-Aid	13,424	261	230	8,701	4,462	0	0	0	0	13,163	0
Special	1,148	1,131	155	14	3	0	0	0	0	17	0
Other	0	0	0	0	0	0	0	0	0	0	0

Classification:

STATE - Major Collector FEDERAL - Major Collector

STATE SYSTEM: Secondary

Estimated Annual Average Daily Traffic (vehicles per day)

5,100 **CURRENT** (2023)

PROJECTED 7,000 (2043)



PROJECT: MD 32, Sykesville Road, 2nd Street to Main Street

<u>DESCRIPTION:</u> Improve intersection geometry, extend turn lanes, and modify access along MD 32 from 2nd Street to Main Street. Improvements include the extension of the northbound MD 32 right-turn lane to 2nd St., modifying the existing 2nd St. intersection to right-in/right-out, extension of the northbound left-turn lane to Johnsville Rd and prohibition of left turns from Johnsville Rd, lengthening the auxiliary lanes between Freedom Ave. and Main St. and a traffic signal warrant analysis for the MD 32/Main St. intersection.

PURPOSE & NEED SUMMARY STATEMENT: This project will improve operations and safety along MD 32 from 2nd Street to Main Street. MD 32 is a main commuter route linking Carroll County with I-70 and the Baltimore-Washington Region. The project is essential for advancing economic development opportunities in southeastern Carroll County. Reducing the turning movements through conversion to right-ins/right-outs and providing channelization will limit conflict points, enhancing safety. Lengthening of auxiliary lanes will provide longer refuge areas, reducing the potential for rear-end collisions.

SMART GROWTH STATUS:	Project Not Location S	Specific	Not Subject to PFA Lav
Project Inside PFA Project Outside PFA PFA Status Yet to Be Determ	nined	Grandfathered Exception Will I Exception Gran	Be Required

SIGNIFICANT CHANGE FROM FY 2023 - 28 CTP: Construction funding has been reduced by \$6.2 million due to the CTP funding deficit, but D&E remains. This project will be evaluated for construction funding as

it advances through the design and engineering phases and additional Transportation Trust Fund revenue becomes available.

STATUS: Engineering underway.

POTENTIA	L FUNDING S	OURCE:		X SPECIAL		X FEDER	AL	GENERAL	OTHER		
	TOTAL										
PHASE	ESTIMATED	EXPENDED	EXPENDED	CURRENT	BUDGET	PRO	JECTED CAS	H REQUIREM	ENTS	SIX	BALANCE
	COST	THRU	IN	YEAR	YEAR	FOF	R PLANNING	PURPOSES C	NLY	YEAR	то
	(\$000)	2023	2023	2024	2025	2026	2027	2028	2029	TOTAL	COMPLETE
Planning	703	703	0	0	0	0	0	0	0	0	0
Engineering	900	0	0	300	400	200	0	0	0	900	0
Right-of-way	0	0	0	0	0	0	0	0	0	0	0
Utilities	0	0	0	0	0	0	0	0	0	0	0
Construction	0	0	0	0	0	0	0	0	0	0	0
Total	1,603	703	0	300	400	200	0	0	0	900	0
Federal-Aid	900	0	0	300	400	200	0	0	0	900	0
Special	703	703	0	0	0	0	0	0	0	0	0
Other	0	0	0	0	0	0	0	0	0	0	0

Classification:

STATE - Minor Arterial

FEDERAL - Other Principal Arterial

STATE SYSTEM: Secondary

Estimated Annual Average Daily Traffic (vehicles per day)

uaj

CURRENT 21,100 - 27,800

(2023)

PROJECTED 37,200 - 42,400

(2043)



PROJECT: MD 26, Liberty Road

<u>DESCRIPTION:</u> Project to provide access, operational, and safety improvements along the MD 26 corridor between the Liberty Reservoir and MD 32 (2.6 miles). Bicycle and pedestrian facilities will be provided where appropriate. Improvements include: an 18-foot raised median, two through lanes with 2-foot inside and 11-foot outside shoulders, and one 15-foot auxiliary lane on MD 26 from Liberty Reservoir to MD 32. Additional targeted improvements include converting eastbound right-turn lane at Georgetown Blvd. to a through/right-turn lane, extending the auxiliary lane from Eldersburg Crossing to west of Homeland Ave, and sidewalks from Carroll Bank to Georgetown Blvd.

<u>PURPOSE & NEED SUMMARY STATEMENT:</u> This project will improve operations and safety along this segment of MD 26.

SMART GROWTH STATUS:	Project Not Location	on Specific	Not Subject to PFA La
Project Inside PFA Project Outside PFA X PFA Status Yet to Be Deta	ermined		athered on Will Be Required on Granted

STATUS: Project on hold. County and State split the cost of planning and the County contributed \$1.0 million towards engineering. In 2020, County and State collaborated to revise project scope.

SIGNIFICANT CHANGE FROM FY 2023 - 28 CTP: None.

POTENTIA	AL FUNDING S	OURCE:		X SPECIAL		X FEDER	AL	GENERAL	X OTHER		
	TOTAL										
PHASE	ESTIMATED	EXPENDED	EXPENDED	CURRENT	BUDGET	PRO	JECTED CAS	H REQUIREM	IENTS	SIX	BALANCE
	COST	THRU	IN	YEAR	YEAR	FOR	RPLANNING	PURPOSES C	DNLY	YEAR	то
	(\$000)	2023	2023	2024	2025	2026	2027	2028	2029	TOTAL	COMPLETE
Planning	496	496	0	0	0	0	0	0	0	0	0
Engineering	1,366	1,366	0	0	0	0	0	0	0	0	0
Right-of-way	0	0	0	0	0	0	0	0	0	0	0
Utilities	0	0	0	0	0	0	0	0	0	0	0
Construction	0	0	0	0	0	0	0	0	0	0	0
Total	1,862	1,862	0	0	0	0	0	0	0	0	0
Federal-Aid	228	228	0	0	0	0	0	0	0	0	0
Special	634	634	0	0	0	0	0	0	0	0	0
Other	1,000	1,000	0	0	0	0	0	0	0	0	0

Classification:

STATE - Intermediate Arterial

FEDERAL - Other Principal Arterial

STATE SYSTEM: Secondary

Estimated Annual Average Daily Traffic (vehicles per day)

ae

CURRENT 15,900 - 32,100

(2023)

PROJECTED 19,500 - 42,300

(2043)

MINOR PROJECTS PROGRAM

(Dollars in Thousands)

STATE HIGHWAY ADMINISTRATION - Carroll County - LINE 4

PROJECT ID	ROUTE NUMBER PROJECT NAME		TOTAL PROGRAMMED COST		STATUS
Intersection Ca	pacity Improvements				
CL3771	MD97	LITTLESTOWN PIKE - BACHMANS VALLEY ROAD TO MD 140 IN WESTMINSTER - PEL STUDY	\$	504	Study Underway
Resurface/Reha	<u>abilitate</u>				
XY9062	-	SAFETY AND RESURFACING IMPROVEMENTS AT VARIOUS LOCATIONS IN CARROLL COUNTY	\$	11,020	FY 2024
CL4052	MD851	SPRINGFIELD AVENUE - DRAINAGE IMPROVEMENTS - MAIN STREET TO WARFIELD ROAD	\$	2,536	Under Construction
XY8062	-	SAFETY AND RESURFACING IMPROVEMENTS AT VARIOUS LOCATIONS IN CARROLL COUNTY	\$	12,378	Under Construction
XY9061	-	SAFETY AND RESURFACING IMPROVEMENTS AT VARIOUS LOCATIONS IN CARROLL COUNTY	\$	17,172	Under Construction
Safety/Spot Imp	<u>orovement</u>				
CL1751	MD140	TANEYTOWN PIKE - INTERSECTION IMPROVEMENTS - AT MAYBERRY ROAD	\$	4,799	Completed
CL3941	MD27	MANCHESTER ROAD - BICYCLE AND PEDESTRIAN ROUTE FROM WEST OF MD 140 TO HAHN ROAD	\$	4,203	Under Construction
<u>Sidewalks</u>					
CL1071	MD31	NEW WINDSOR ROAD - SIDEWALK IMPROVEMENTS FROM LAMBERT AVENUE TO EAST OF CHURCH STREET	\$	2,177	Design Underway
Transportation	Alternatives Program				
CLTAP1 CLNEW3	Ī	MT. AIRY OLD MAIN LINE TRAIL WASHINGTON ROAD - SIDEWALK UPGRADES FOR ADA COMPLIANCE FROM WASHINGTON LANE TO KATE WAGNER ROAD - SAFE ROUTES TO SCHOOL	\$ \$	321 143	Completed FY 2024